



















NOTE: SOILS BENEATH AGGREGATE SHALL BE SCARIFIED OR TILLED PRIOR TO INSTALLATION OF AGGREGATE.




DRIVEWAY PAVEMENT
NOT TO SCALE



DRIVEWAY CROSS SECTION
NOT TO SCALE



24" LEACHING GALLERY H 20 RATED
NOT TO SCALE




12" LEACHING GALLERY H 20 RATED
NOT TO SCALE



FCE Project #	2168	Date Performed:	10/6/2023
Client:	Old Driftway LLC		
Location:	0 Mountain Road, Wilton		
Observed by:	Wayne D'Avanzo		
Test Hole 1:	0-4" Topsoil	4-38" Tan Fine Gravel, rocky	
	No Ground Water	No Matting	
	No Ledge	Compacted at 38"	
		Roots to 30"	
Test Hole 2:	0-4" Topsoil	4-38" Tan Fine Gravel	
	No Ground Water	No Matting	
	No Ledge	Ledge @ 24"	
		Roots to 19"	
Test Hole 3:	0-6" Topsoil	5-43" Tan Fine Gravel, rocky	
	No Ground Water	No Matting	
	No Ledge	No Matting	
		Roots to 28"	
Test Hole 4:	0-4" Topsoil	4-20" Brown Fine Gravel	
	No Ground Water	No Matting	
		Ledge @ 20"	
		Roots to 12"	



10-14-23
date



REV. 12/13/23: PER ENGINEERING COMMENTS.
REV. 11/10/23: PER ENGINEERING COMMENTS.
OLD DRIFTWAY LLC
0 MOUNTAIN ROAD WILTON, CONNECTICUT
CIVIL ENGINEERS
2168 project
FAIRFIELD COUNTY ENGINEERING L.L.C.
60 WINFIELD STREET, NORWALK, CONNECTICUT 06855 PH: (203) 831-8005 FAX: (203) 831-8006
6 OF 6 sheet



REV. 12/13/23: PER ENGINEERING COMMENTS.
REV. 11/10/23: PER ENGINEERING COMMENTS.

OLD DRIFTWAY LLC

0 MOUNTAIN ROAD	WILTON, CONNECTICUT
-----------------	---------------------

RIGHT OF WAY PLAN SOUTH

CIVIL ENGINEERS


2168
project

FAIRFIELD COUNTY ENGINEERING L.L.C.

OF 6
sheet

60 WINFIELD STREET, NORWALK, CONNECTICUT 06855 PH: (203) 831-8005 FAX: (203) 831-8006

168 231213ROW



CONSTRUCTION SEQUENCE

ANY NECESSARY ROCK REMOVAL SHALL BE BY MEANS OF CHIPPING. REMOVED MATERIAL SHALL BE REMOVED FROM SITE IMMEDIATELY AND NOT STOCKPILED. HOURS OF OPERATION SHALL BE LIMITED TO 8 AM TO 6 PM, MONDAYS THROUGH FRIDAY, SUBJECT TO ANY FURTHER REGULATION FROM THE TOWN OF WILTON.







PRIOR TO THE ISSUANCE OF A CERTIFICATE OF OCCUPANCY, A CERTIFIED AS-BUILT DRAWING AND CERTIFIED LETTER SIGNED BY A PROFESSIONAL ENGINEER INDICATING THAT ALL WORK WAS COMPLETED IN ACCORDANCE WITH THE DESIGN PLANS SHALL BE SUBMITTED TO THE TOWN OF WILTON.

CROSSING TO BE CONSTRUCTED DURING DRY SEASON (AUGUST-SEPTEMBER) AND OUTSIDE OF THE AMPHIBIAN BREEDING SEASON

INSTALL SILT FENCING AND HAYBALES AS SHOWN ON PLAN. SECURE CROSSING WITH PLYWOOD. FILL AND STONE WILL BE BROUGHT TO THE NORTH END OF THE CROSSING. TWO EXCAVATORS WILL BE BROUGHT TO THE NORTH END. ONE WILL POSITION THE CULVERTS AS SHOWN ON THE PLAN AS IT RETURNS TO THE SOUTH END. THE EXCAVATOR ON THE NORTH WILL FILL BETWEEN CULVERTS, WORKING TO THE SOUTH, AS THE SOUTH MACHINE DOES THE SAME WORKING TO THE NORTH. THE POSTS FOR THE GUIDE RAILS WILL BE INSTALLED TO COINCIDE WITH THE SOLID PORTION OF EACH CULVERT. THE PROCESS BASE FOR THE POROUS DRIVEWAY WILL BE PLACED ACROSS THE AREA. THE POROUS PAVEMENT WILL BE PLACED.

- GENERAL CONSTRUCTION NOTES:
- CONSTRUCTION AND STRUCTURES SHALL COMPLY WITH ALL MUNICIPAL OR STATE REQUIREMENTS. ALL WORK SHALL BE CERTIFIED BY A REGISTERED PROFESSIONAL ENGINEER, TO THE SATISFACTION OF THE ENGINEERING BUREAU, THAT CONSTRUCTION IS IN ACCORDANCE WITH THESE PLANS.
 - THE ENGINEERING BUREAU OF THE DEPARTMENT OF PUBLIC WORKS AND THE ENGINEER OF RECORD SHALL BE NOTIFIED THREE DAYS PRIOR TO THE COMMENCEMENT OF EACH PHASE OF CONSTRUCTION.
 - NO CERTIFICATE OF CONFORMANCE TO STANDARDS SHALL BE ISSUED BY THE DESIGN ENGINEER IF PROPER NOTICE IS NOT PROVIDED FOR INSPECTIONS OR IF INSPECTIONS ARE NOT MADE PRIOR TO THE COMMENCEMENT OF EACH PHASE OF CONSTRUCTION.
 - SUBSURFACE STRUCTURES AND UTILITIES HAVE BEEN DETERMINED FROM EXISTING RECORDS AND ARE NOT GUARANTEED TO BE COMPLETE OR ACCURATE. IN ORDER TO AVOID CONFLICT OF THE PROPOSED WORK AND EXISTING UTILITIES, THE CONTRACTOR SHALL LOCATE EXISTING UTILITIES BY EXCAVATING TEST HOLES. IF THE CONTRACTOR DETERMINES THAT A CONFLICT EXISTS, HE SHALL IMMEDIATELY NOTIFY THE ENGINEER, WHO WILL MAKE THE NECESSARY ADJUSTMENTS.
 - EXISTING PROPERTY AND UTILITY INFORMATION WAS TAKEN FROM A SURVEY BY ALL SEASONS LAND SURVEYING TITLED "TOPOGRAPHIC SURVEY PREPARED FOR OLD DRIFTWAY LLC", DATED MARCH 30, 2023.
 - THESE PLANS ARE FOR MUNICIPAL OR STATE AGENCY APPROVAL ONLY. NOT FOR CONSTRUCTION.
 - NO PIPE SHALL HAVE A BEND OF GREATER THAN 45 DEGREES.
 - THE CONTRACTOR SHALL NOTIFY "CALL BEFORE YOU DIG" AT 1-800-422-4455, OR OTHER APPROPRIATE CONTACT POINT PRIOR TO START OF CONSTRUCTION.
 - ALL UTILITY LOCATIONS ARE APPROXIMATE. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CONFIRM THE LOCATION OF THE UTILITIES IN THE FIELD BY WATEREVEER MEANS HE DEEMS PRUDENT.
 - THIS DESIGN CONFORMS TO APPLICABLE CODES AND ACCEPTED PRACTICE, NO OTHER WARRANTY IS EXPRESSED OR IMPLIED.

- SEDIMENTATION AND EROSION CONTROL NOTES:
- LAND DISTURBANCE SHALL BE KEPT TO A MINIMUM. PERMANENT STABILIZATION SHALL BE SCHEDULED AS SOON AS PINK GRASSES ARE ESTABLISHED.
 - ALL DISTURBED AREAS SHALL BE FINE GRADED AND SEEDING WITH AN APPROVED SEED MIXTURE. COVER NEWLY SEEDING AREAS WITH MULCH HAY OR SALT HAY.
 - ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE STANDARDS AND SPECIFICATIONS OF THE 2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL HANDBOOK.
 - ALL CONTROL MEASURES SHALL BE MAINTAINED IN EFFECTIVE CONDITION THROUGHOUT THE CONSTRUCTION PERIOD. CHECK AFTER EACH STORM EVENT.
 - ADDITIONAL CONTROL MEASURES SHALL BE INSTALLED DURING THE CONSTRUCTION PERIOD, IF REQUIRED BY TOWN AUTHORITIES.
 - SEDIMENT DEPOSITS REMOVED FROM FILTER BARRIERS SHALL BE PLACED IN FILL AREAS OR SPREAD WHERE THERE IS PROPOSED VEGETATIVE COVER. ANY SEDIMENT DEPOSITS REMAINING AFTER THE FILTER BARRIER IS REMOVED SHALL BE FINE GRADED AND PLANTED ACCORDING TO PLAN.
 - THE SITE CONSTRUCTION CONTRACTOR IS ASSIGNED THE RESPONSIBILITY FOR IMPLEMENTING THIS EROSION AND SEDIMENT CONTROL PLAN. THIS RESPONSIBILITY INCLUDES THE INSTALLATION AND MAINTENANCE OF CONTROL MEASURES, REPORTING ALL CHANGES ON THE CONSTRUCTION SITE OF THE REQUIREMENTS AND OBJECTIVES OF THE PLAN NOTING THE PLANNING AND ZONING OFFICE (AND/OR THE CONSERVATION COMMISSION) OF ANY TOWN OF THIS RESPONSIBILITY AND PROVIDING A COPY OF THE EROSION AND SEDIMENT CONTROL PLAN IF THE TITLE TO THE LANDS TRANSFERRED TO A NEW OWNER.



REV. 12/13/23: PER ENGINEERING COMMENTS. REV. 11/10/23: PER ENGINEERING COMMENTS.	
OLD DRIFTWAY LLC	
0 MOUNTAIN ROAD WILTON, CONNECTICUT	
RIGHT OF WAY PLAN	
CIVIL ENGINEERS	2168 project
FAIRFIELD COUNTY ENGINEERING L.L.C.	
60 WINFIELD STREET, NORWALK, CONNECTICUT 06855 PH: (203) 831-8005 FAX: (203) 831-8006	
1 OF 6 sheet	

FAIRFIELD COUNTY ENGINEERING, LLC
CIVIL ENGINEERS
60 WINFIELD ST.
NORWALK, CONNECTICUT 06855
(203) 831-8005 FAX: (203) 831-8006
E-mail to: wayne@fairfieldce.com

December 13, 2023

Please see the following in response to the Engineering comments received December 13, 2023.

1. No grading or structures are proposed on any property other than the accessway. The retaining walls will be constructed of filled concrete block and will not require formwork. The trees can be cut and stumps ground to the property line as needed, with no disturbance to adjacent properties. As is, there are only 5 trees that are shown to be removed near the property lines, and none in the Upland Review Area.
5. Conservation application is in progress.
6. Fire Marshall comments were addressed; driveway is 10' wide, 15' in other sections; turnaround is provided; box culverts are HL 93 rated, greater than the gross weight of the fire truck; the angle over the box culverts is 28 degrees, less than some Town roads. clearly.
8. Operations and Maintenance plan previously submitted.
13. Revised on plan.
14. Provided on plan.
15. Correct. Overflow will occur at the grates of the driveway drain, and not over the galleries. These are at a higher elevation than the tops of the galleries. This is more conservative than as modeled in HydroCAD; will overflow later and when more water volume is retained than the model shows.
16. No manufacturer per se; coarse particle separators are 2' x 2' precast concrete structures, with a minimum of 2' sumps, and a downturned 90 degree elbow placed on any outlet pipe. There is no size calculation required; it is simply a pass through structure, allowing for sediment to settle. The capacity of the pipes connecting provide the flow limit or capacity.

Respectfully submitted,

Wayne D'Avanzo, P.E.
Principal
FAIRFIELD COUNTY ENGINEERING, LLC

Operations and Maintenance Plan

0 Mountain Road

October 6, 2023

Scope:

The purpose of the Operations and Maintenance Plan is to ensure that the porous pavement installed at 0 Mountain Road is maintained in operational condition throughout the life of the project. The service procedures associated with this plan shall be performed as required by the parties legally responsible for their maintenance.

Recommended Frequency of Service:

As further defined below, all stormwater components should be checked on a periodic basis and kept in full working order. Ultimately, the required frequency of inspection and service will depend on runoff quantities, pollutant loading, and clogging due to debris. At a minimum, we recommend that all stormwater components be inspected and serviced twice per year, once before winter begins and once during spring cleanup.

Service Procedures:

Porous Pavement (Pervious Concrete, Porous Asphalt):

- a. Clean and vacuum (Regenerative Air Vacuum for Permeable Interlocking Concrete Pavers) the porous pavement upon the completion of construction.
- b. Check for standing water on the surface of the pavement after a precipitation event. If standing water remains within 30 minutes after rainfall had ended, cleaning of porous pavement is recommended.
- c. Vacuum sweeper shall be used regularly to remove sediment and organic debris on the pavement surface. The sweeper may be fitted with water jets.
- d. Pavement vacuuming should occur during spring cleanup following the last snow event to remove accumulated debris, at a minimum.
- e. Pavement vacuuming should occur during fall cleanup to remove dead leaves, at a minimum.
- f. Power washing can be an effective tool for cleaning clogged areas. See manufacturer's specifications.
- g. Check for debris accumulating on pavement, especially debris buildup in winter. For loose debris, a power/leaf blower or gutter broom can be used to remove leaves and trash.
- h. Any additional maintenance required per the manufacturer's specifications shall also be completed.

Disposal of Debris and Sediment:

All debris and sediment removed from the stormwater structures and bioretention/biofiltration basins shall be disposed of legally. There shall be no dumping of silt or debris into or in proximity to any inland or tidal wetlands.

Maintenance Records:

The Owners(s) must maintain all records (logs, invoices, reports, data, etc.) and have them readily available for inspection at all times.