

THIS DOCUMENT IS INCOMPLETE AND IS RELEASED TEMPORARILY FOR PROGRESS REVIEW ONLY. IT IS NOT INTENDED FOR BIDDING OR CONSTRUCTION PURPOSES.

**Fuller
Development
LLC**

64 Danbury
Road

Wilton,
Connecticut

SCALE: AS NOTED

LP-2

NOTES:

1. EXISTING AND PROPOSED SITE INFORMATION TAKEN FROM A DIGITAL AUTOCAD SITE PLAN SUPPLIED BY TIGHEBOND. REFER TO THESE SITE PLANS FOR ADDITIONAL INFORMATION.
2. CONTRACT "CALL BEFORE YOU DIG," AT 1-800-922-4455 TO HAVE UNDERGROUND UTILITY LINES MARKED BY THEM PRIOR TO START OF ANY EXCAVATION WORK.
3. SEED AREAS AT THE METHODS AND 15% THE APPLICATION RATE RECOMMENDED BY THE MANUFACTURER. THE SEED SHALL BE SPREAD ON THE PROPOSED AREAS BY HAND OR USING A SEED SPREADER. THE SEED SHALL BE APPLIED TO THE PROPOSED AREAS AT A RATE OF 2 LBS./ACRE. SEED AREAS SHALL BE STRAW OR COMMERCIAL WOOD CHIP PRODUCTS APPLIED BY HAND OR BY HYDROSEEDING ON SLOPES LESS THAN 10%. SEED AREAS ON SLOPES 10% OR GREATER THAN 10% SHALL BE COVERED WITH A PLASTIC FREE AND 100% BIODEGRADABLE (INCLUDING ANCHOR STAPLES) EROSION CONTROL BLANKET. A MINUSE COVER OF PERENNIAL RYE GRASS AT THE RATE OF 40 LBS./ACRE SHALL BE ADDED TO THE SEED MIX ON SLOPES OF EXCESS OF 10% AND AS SPECIFIED. SEED MIX SUBSTITUTIONS SHALL BE EQUIVALENT TO THAT SPECIFIED AND APPROVED BY THE PROJECT LANDSCAPE ARCHITECT PRIOR TO USE. UNLESS OTHERWISE SPECIFIED, MAINTAIN SEEDING AREAS AS RECOMMENDED BY THE MANUFACTURER. EXCEPT FOR LAWN AREAS, DO NOT FERTILIZE AREAS TO BE SEEDD UNLESS SPECIFIED BY THE MANUFACTURER. SEED AREAS AS PER THE FOLLOWING SCHEDULE:
6. A. LAWN: SEED LAWN AREAS WITH "SMART SEED NORTHEAST" MIX BY PENNINGTON SEED, INC. OR APPROVED EQUIVALENT. APPLY SOIL AMENDMENTS AS RECOMMENDED BY THE MANUFACTURER.
6. B. WETLAND BUFFERS (UPLAND AREAS):
 1. SEED THIS AREA WITH "NEW ENGLAND CONSERVATION / WILDLIFE SEED MIX" BY FROM NEW ENGLAND WETLAND PLANTS, INC. (413-548-8000). IF SPECIFIED SEEDING CAN NOT OCCUR DUE TO SEASONAL AND WEATHER CONDITIONS, TEMPORARY SEED DISTURBED UPLAND AREAS WITH A MIXTURE OF ANNUAL RYE AT 20 LBS./ACRE, PERENNIAL RYE AT 20 LBS./ACRE, AND REDTOP AT 2 LBS./ACRE AND DISTURBED WETLAND AREAS WITH ANNUAL RYE AT THE RATE OF 30 LBS./ACRE. MULCHING, WITHOUT SEEDING, MAY BE USED DURING THE NON-GROWING SEASON IN ACCORDANCE WITH THE THE CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL (2002).
 2. EXACT LOCATION OF PROPOSED PLANTINGS AND SPECIES TYPES MAY VARY FROM THIS PLAN BASED ON ACTUAL FIELD CONDITIONS.
 3. SPRAY NEW PLANTINGS IMMEDIATELY AFTER INSTALLATION WITH A WHITE-TAILED DEER REPELLENT AND CONTINUE AS NEEDED TO MAINTAIN PLANTS FREE OF SIGNIFICANT DEER BROWING.
 4. PLANT SPECIES SUBSTITUTIONS MAY BE MADE WITH THE APPROVAL OF THE PROJECT LANDSCAPE ARCHITECT AND TOWN OF WILTON PRIOR TO PLANTING. SUBSTITUTED PLANTS SHALL BE AT AN EQUAL OR GREATER SIZE AS NOTED USING A SIMILAR TYPE PLANT.
 5. MUCH AREAS AROUND NEW TREES AND SHRUBS WITH A 3" THICK LAYER OF SHREDDED CEDAR BARK MULCH. NEW TREES SHALL EACH HAVE A 5 MIN. DIA. MULCHED BED AND NEW SHRUBS SHALL EACH HAVE A MINIMUM 3" DIAMETER MULCHED BED. AREAS WITHIN 4' OF TREE TRUNKS SHALL BE MAINTAINED FREE OF MULCH.
 6. PLANTING METHODS SHALL BE IN ACCORDANCE WITH THE "AMERICAN STANDARDS FOR NURSERY STOCK," LATEST EDITION, AS PUBLISHED BY THE AMERICAN NURSERY & LANDSCAPE ASSOCIATION.
11. THIS PLAN FOR PLANTING PURPOSES ONLY. SEE PLANS BY OTHERS FOR ADDITIONAL INFORMATION.
12. NONNATIVE INVASIVE MANAGEMENT: REMOVE JAPANESE BARBERY, BURNINGBUSH, ASIAN Bittersweet, MULTIFLORA ROSE AND NOTED NORWAY MAPLES UNDER 3" CALIPER FROM WETLAND AND ADJACENT UPLAND AREAS BY HAND PULLING, OR IF NOT PRACTICAL, CUTTING THE PLANTS DOWN TO JUST ABOVE GRADE AND APPLYING AN APPROPRIATE HERBICIDE, SUCH AS ROUNDUP IN UPLAND AREAS AND IMAZAPR (TRADE NAME: HERBATON) IN WET CONDITIONS. INTO THE STEEP WELLS. SEVERAL TREATMENT MAY BE REQUIRED. THE PERIOD BETWEEN JULY AND OCTOBER IS THE PREFERRED TIMING TO APPLY HERBICIDE. NONNATIVE INVASIVE PLANTS SHALL BE MANAGED FOR A MINIMUM OF FIVE YEARS.

NONNATIVE INVASIVE SPECIES CONTROL NOTES:


1. CONTROL PERIOD OF NONNATIVE INVASIVE PLANTS TO BE ONGOING OVER A FIVE (5) YEAR PERIOD (OR LONGER).
2. THE LANDSCAPE CONTRACTOR SHALL CONTACT THE PROJECT ENVIRONMENTAL CONSULTANT WITH ANY QUESTIONS REGARDING THE CONTROL OR IDENTIFICATION OF INVASIVE NONNATIVE SPECIES.
3. THE LANDSCAPE CONTRACTOR SHALL FOLLOW THE METHODS AND RECOMMENDATIONS RECOMMENDED BY THE HERBICIDE MANUFACTURER AND COMPLY WITH ALL FEDERAL, STATE AND LOCAL LAWS. A PERMIT FROM DEEP IS REQUIRED FOR ANY PESTICIDE APPLICATION TO A BODY OF WATER.
4. ALL CUT OR PULLED INVASIVE NONNATIVE PLANT MATERIALS SHALL BE DISPOSED APPROPRIATELY AND COMPLY WITH THE 2004 DEEP /UCJONN "GUIDELINES FOR DISPOSAL OF TERRESTRIAL INVASIVE PLANTS." ALL CUTTINGS SHALL BE COLLECTED AND PLACED ONSITE ON A PLASTIC TARP (OR ON AN ASPHALT PAVED AREA) AND SUN DRIED UNTIL DEAD. -VOID CUTTINGS FROM BEING IN CONTACT WITH ANY SOIL. DEAD PLANTS SHALL BE BAGGED AND DEPOSITED AT AN INCINERATOR WASTE FACILITY (NOT A COMPOSTING FACILITY).
5. START CONTROL OF INVASIVE PLANT SPECIES PRIOR TO THE START OF EARTH MOVING ACTIVITIES. CONTROL NONNATIVE INVASIVE SPECIES AS FOLLOWS:
 - A. FOR JAPANESE KNOWTWEED, EUONIMUS, ASATIC BITTERSWEET, AND NORWAY MAPLES CONTROL.
 - STEP 1# (PRIOR TO HERBICIDE PRETREATMENT) CUT PLANT DOWN TO GRADE LEVEL DURING THE GROWING SEASON (LATE SUMMER OR EARLY FALL IS PREFERABLE). REMOVE ASATIC BITTERSWEET ROOTS IF FEASIBLE. DISPOSE OF CUT PLANT MATERIAL AS OUTLINED ABOVE.
 - STEP 2# IMMEDIATELY AFTER CUTTING, TREAT CUT STEMS WITH AN APPROPRIATE HERBICIDE (SUCH AS ROUND-UP) AT THE RATE AND METHODS RECOMMENDED BY THE MANUFACTURER. CARE SHALL BE TAKEN TO AVOID HERBICIDE CONTACT WITH NATIVE OR OTHER DESIRABLE VEGETATION.
 - STEP 3# CHECK CONTROL AREA MONTHLY DURING THE GROWING SEASON FOR NEW GROWTH. SPOT TREAT NEW GROWTH WITH AN APPROPRIATE HERBICIDE AS NEEDED FOR CONTROL.
 - B. CARE SHALL BE TAKEN TO AVOID HERBICIDE CONTACT WITH NATIVE OR OTHER DESIRABLE VEGETATION. IN AREAS WHERE NATIVE PLANTS ARE GROWING NEAR PLANTS TO BE CONTROLLED THE HERBICIDE SHALL NOT BE SPRAYED ONTO THE TARGET PLANTS. IN THESE AREAS THE HERBICIDE SHALL BE APPLIED WITH A BRUSH OR CLOTH.
- 6.

NONNATIVE INVASIVE DISPOSAL:


PLANT DISPOSAL

1. ALL CUT OR PULPED INVASIVE NONNATIVE PLANT MATERIALS SHALL BE DISPOSED APPROPRIATELY AND COMPLY WITH THE 2004 DEEP LULUON GUIDELINES FOR DISPOSAL OF TERRESTRIAL INVASIVE PLANTS. ALL CUTTINGS SHALL BE COLLECTED AND PLACED ONCE ON THE SOIL, IF FEASIBLE, DO NOT REMOVE PULPED OR CUT NONNATIVE INVASIVE PLANTS FROM THE SITE UNTIL DEAD. EXCEPT FOR TUBEROUS PLANTS, SUCH AS JAPANESE KNOTWEED AND PHAGMITES, NONNATIVE INVASIVE PLANTS PULLED OR CUT SHALL BE LEFT ON THE GROUND SURFACE IN A SUNNY LOCATION FOR THEM TO DRY. TUBEROUS WEED PLANTS SHALL BE LEFT SOIL FREE IN THE SUN ON AN IMPERVIOUS BARRIER (SUCH AS BLACK PLASTIC, DOWNEYARD AND WALSH) UNTIL DEAD SO THAT THEY DO NOT RE-SPROUT.
2. IF PLANTS HAVE TO BE REMOVED FROM THE SITE BEFORE THEY ARE DEAD, THEY SHALL BE BAGGED AND DEPOSITED AT AN INCINERATOR WASTE FACILITY (NOT A COMPOSTING FACILITY).

DIRECTIONAL SIGN




SCALE: NTS



- NOTE:
1. LIGHT FIXTURE & POLE BY BEGA PRODUCTS.
 2. POLE AND FIXTURE COLOR SHALL BE BLACK.
 3. INSTALL LIGHT POLE AND FOOTING PER MANUFACTURER'S RECOMMENDATIONS.

POLE LIGHT (TYP.)


SCALE: NOT TO SCALE



- NOTE:
1. FENCE SHALL BE MADE OF VINLY.
 2. COLOR SHALL MATCH BUILDING COLOR


LATTICE SCREENING FENCE
(4' HT.) FOR AIR HANDLERS

SCALE: NOT TO SCALE



FREE STANDING SIGN

SCALE: NTS




LANDSCAPE LIGHTING NOTES (TYP.):

1. FOOTCANDLE LIGHTING LEVELS FOR THIS PROJECT WERE PREPARED BY OTHERS.
2. SITE LIGHTING INFORMATION AND LIGHTING PLANS PREPARED BY ENVIRONMENTAL LAND SOLUTIONS, LLC ARE DESIGNED FOR GENERAL LANDSCAPE AESTHETIC PURPOSES ONLY. LIGHTING INFORMATION SHOWN ON THIS PLAN SHALL NOT BE USED FOR SECURITY OR SAFETY PURPOSES.
3. THIS PLAN ASSUMES THAT THE BUILDING WILL HAVE WALL MOUNTED FIXTURES (BY OTHERS) TO LIGHT THE FACADE AND ADJACENT LANDSCAPE AREAS (INCLUDING WALKS AND DOORS).
4. INSTALL LIGHT FIXTURES AS RECOMMENDED BY THE MANUFACTURER.
5. LIGHT POLES LOCATED WITHIN LANDSCAPE AND PEDESTRIAN AREAS SHALL BE ON A BASE FLUSH WITH GRADE LOCATED A MINIMUM OF 3' FROM THE EDGE OF VEHICLE PAYMENT IF FEASIBLE.

BOLLARD LIGHT (TYP.)


SCALE: NOT TO SCALE



- NOTE:
1. FENCE COLOR SHALL MATCH BUILDING.

VINYL SCREENING FENCE (TYP.)

SCALE: NOT TO SCALE



SIGN BEHIND EXISTING ENTRANCE WALL

SCALE: NTS