



Proposed Site Lighting: Bank Of America

117 Old Ridgefield Rd, Wilton CT

CT2-255 Rev. 4

To whoever this may concern, the changes to our lighting design are as follows:

- 2 new poles (UGX1) in the front of the property have been removed from the scope of work.
- The tree in the front of the property that we had initially planned on removing has been removed from the scope of work, no landscaping will be removed only pruned where it may interfere with light.
- All lighting has been changed from 4000 kelvin to 3000 per the board's request
- One additional wall mount fixtures (USJ2) has been added on the front of the building to compensate for removing the pole lights, this matches the other proposed fixtures depicted on the cut sheets already submitted.
- An overall reduction in illumination in the front of the property going from the highest estimated value of 13.4FC to 9.5FC, tapering down to 0.1FC at the property line on Old Ridgefield Rd.