



***Town of Wilton***  
**High School Track Renovations**

---

NCPA Bid Proposal

1/19/2021



28 Commerce Park Rd PO Box 1100 Pocasset, MA 02559

(508) 759-5636 FAX (508) 563-7915

January 19, 2021

Town of Wilton  
Parks and Recreation Department  
Comstock Community Center  
180 School Road  
Wilton, CT 06897

**High School Track Renovations  
NCPA Bid Proposal  
Wilton, CT**

***Base Bid: Track Replacement***

**General: This proposal is for the complete replacement of the existing running track surface at the Wilton High School Running Track, located in Wilton, CT. Included in this option is the removal and disposal of the existing surface, the removal of the existing pavements, new asphalt pavements, new in-ground equipment, miscellaneous minor site improvements and a new two-tone, BSS-300 embedded texture track system. Includes track oval and D areas (approximately 6,700 sy)**

***Cape & Island Tennis & Track to Provide (General):***

Perform work included and in accordance with project documents distributed by Stantec Planning and Landscape Architecture dated "December 2020." CIT&T acknowledges bidding requirements, specifications and general conditions contained in those documents.

***Work includes (but not limited to):***

- Provide insurances and performance and payment bond per specifications.
- Survey existing track layout and topography.
- Protect perimeter structures (fence, pavements, synthetic turf field etc).
- Protect existing landing pits, ball stop netting system and flag pole.
- Remove & dispose of the existing synthetic surface.
- Clean out and inspect stone drainage trench.
- Remove & dispose existing track asphalt base. Not to exceed average overall thickness of 3.5"
- Install electrical conduits and hand holes per plan.
- Perform repairs to damaged section of concrete channel drain encasement.
- Clean and inspect existing channel drain.
- Install .5" of 3/8" dense grade or stone dust to assist with laser grading as needed.

- Laser grade base to within 1/4" in 10'.
- Install 3.5" of bituminous concrete in 2 lifts.
- Install in-ground pole vault box.
- Install 14mm blue and grey **BSS-300 embedded texture** polyurethane sandwich system (an IAAF certified product), manufactured by Beynon Sports Surfaces of Hunt Valley, MD.
- Install NFHS certified line markings.
- Project shall be managed by an **ASBA Certified Track Builder**
- "As Built" layout drawing for striping and slope
- Seven Year Track Surface Warrantee
- Prevailing wages and certified payroll.

**Price for Base Bid:** **\$918,700**  
**NCPA Bid Unit Price for Specified Track Surface (Included in Base Bid)**

**Add Alternate 1 – Blue Track with Grey D Zones**

CIT&T to install blue track and grey D zones.

**Add Price for Alternate 1:** **\$42,300**  
**For Alternate 1 Initial Here:** \_\_\_\_\_

**Add Alternate 2 – Grey Exchange Zones**

CIT&T to install exchange zones in alternate color (grey) from track. This price includes layout by line striper and additional labor to install. (Must also choose Alt. 1)


**Add Price for Alternate 2:** **\$12,300**  
**For Alternate Initial Here:** \_\_\_\_\_

**Payment Schedule to be as Follows:**

Deposit of 10% due upon acceptance of proposal and delivery of proof of insurance and bond.

Upon approval of agreed upon schedule of values, payment shall be made according to completion of scheduled items bi-monthly.

Balance to be paid upon completion.

Authorized Signature:  Date: 1 / 19 / 2021  
 Kristoff Eldridge, CTB  
 President

**Acceptance of Quote**

If the foregoing meets with your acceptance, kindly sign and return the attached copy of our proposal. Upon its receipt it is understood the foregoing, including the terms and conditions set forth above, will constitute the full and complete agreement between us.

Authorized Signature: \_\_\_\_\_ Date: \_\_\_\_/\_\_\_\_/\_\_\_\_

This quote expires thirty days from the date hereof, but may be accepted at any later date at the sole option of Cape & Island Tennis & Track.